

Bid #27-1 North Pens of the Outdoor Arena	Mayfield Ag	
	918-331-5403	
	Misc #29306	
	Specs	
ARENA FENCE DEMO OLD PENS AND ALLEY FENCE – 6 RAIL TOP RAIL WILL BE 2 3/8" PIPE, APPROX 1615 LINEAR FT 5 RAILS BELOW WILL BE 1 3/8" PIPE WITH AT LEAST EVERY SIXTH LINE POST CONCRETED NO LESS THAN 3' IN THE GROUND Corner Posts – 4" pipe and concreted no less than 3' in the ground. Gates: 4' – 1 6' – 1 10' – 3 12' – 3 16' – 3 20' – 2 ALL GATE POSTS WILL BE OVERHEAD 10' OVERHEAD ON 4', 6', 10', 12', 16' GATES 14' OVERHEAD ON 20' AND 40' Project Timeline Constraints: • Start Date after October 5, 2026 (due to prior scheduling) • Completion Date before May 1, 2027 CONCRETE LABOR	Demolition of the outdoor arena and alleyway. Rebuild with all new materials. This project will meet the specifications of Bid Packet #27-2. All materials and labor are provided by Mayfield Ag.	\$83,564.00
<u>TOTAL</u>		\$83,564.00